

ADDENDUM NO. 4

PART I - GENERAL

1.1 PROJECT INFORMATION

- A. Project Name: Renovations and Addition to Old City Hall, Quincy, MA
- B. Owner: City of Quincy
- C. Architect: Holmes & Edwards, Inc.
- D. Architect Project Number: #1003
- E. Date of Addendum: July 22, 2013

1.2 NOTICE TO BIDDERS

- A. This Addendum is issued to all General Contractors and Subcontractors pursuant to the Instruction to Bidders and Conditions of the Contract. This Addendum serves to clarify, revise, and supersede information in the Project Manual and Drawings. Portions of the Addendum affecting the Contract Documents will be incorporated into the Contract by enumeration of the Addendum in the Owner/Contractor Agreement.
- B. The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form.

SPECIFICATIONS

Section 044300 – Stone Masonry

Description of Work 1.2A, Add Note 2: “Granite paver flooring noted in Finish Schedule in both the Lobby (111) and Vestibule (112) are the responsibility of this section. Note: Pavers to be of size, shape and thickness as shown on the drawings and shall also be salvaged granite as described below.”

Under Part 2- Products, Insert Item G: “The salvaged granite referenced in Section 040120 Masonry Restoration and Cleaning, Part 1 General, Description of Work 1.2, Item 6, is available from the Owner at two different locations within the City of Quincy. Slabs of granite of sizes adequate to conform to the sizes of all exterior stone units and floor pavers in the new addition must be assessed by this subcontractor, trucked to a facility where the appropriate sizes of stone can be cut and finished and prepared for installation into the work. Trucking to and from the cutting facility and all costs associated with the cutting of this salvaged granite to be part of the work of this section.”

Section 260000 – Electrical

The Electrical Contractor shall be responsible for temporary electrical and lighting per Section 260000.