SECTION 00 91 13

ADDENDUM NO. 2

NOTICE is hereby given that the **Bidding Documents have been modified and replacement pages issued** herewith. Replacement pages have an **Issue Date of October 27, 2014;** contain reference to "**Addendum 2**" in the footer, and text changes for additions identified by **double underline** and deletions identified by ~~Strikeout~~.

Specifications: Replacement pages include:

- Section 00 43 22, Unit Prices Form – Page 2

NOTICE is hereby given of the following **additional information and clarifications** which do not cause change to the Bidding Documents. The answers below are provided in response to questions and comments submitted by Bidders.

1. *There are no inverts for the 12" RCP drain line. Please provide the pipe inverts.*

Answer: The existing invert as depicted on plan sheet EX-100 is 7.81. The proposed pipe is to connect to the existing invert elevation and be laid at 1%. The invert elevation of the upgradient end of the proposed pipe will be 8.9.

2. *Although the specification under "Measurement & Payment" says that the site preparation items are incidental to all the other payment items, should a bid item be added to the bid form to cover site preparation?? If there is no bid item added then in what bid item do you want us to include these costs. Bear in mind that if we spread these costs over the current bid items, the actual amount of units paid for in each item that contains the site preparation costs will be inflated or deflated based on the actual units paid for. The other option is to put these costs into the Mobilization/ Demobilization payment item which is a lump sum item. Please advise where you want these costs to be covered.*

Answer: It is recognized that items indicated as incidental to the project have a cost. Each bidder is to determine the appropriate location within the unit price bid items to reflect any costs associated with incidental items of the project.

3. *Under section "Specific Project Requirements and Procedures"- Section 3.03 A2 refers to adequate grass growth of 3" before removal of erosion control. There is no bid item for any loam and seeding for this project. Is loam and seeding required, and if so please indicate where.*

Answer: Loam and seeding are not required for this project.

4. Is the wall drain pipe to be 4" or 6"? The detail on C400 shows 4" while the specification Page 505 section 3.04B says 6"

Answer: The wall drain pipe shall be provided as indicated on the detail on plan sheet C-400, 4 inch diameter perforated PVC.

5. The construction road seems to go through a wetland area or wetland trench prior to reaching the field area. This will require filling in a 20-25 foot wide wetland area. Is the gully that requires filling to construct the construction road considered a wetland area? If so, how are we to proceed in the construction of the road? Will special permits be required? Will wetland replication be required?

Answer: The area in question is an isolated vegetative wetland. The Owner will secure any environmental permits necessary for the project. Wetland replication is not included in this contract.

6. Please confirm our understanding of the following;

- *All fill materials will be delivered by the City (via Lorusso-Bristol Stone Corporation of Weymouth MA).*
  - *This includes the material required for the construction entrance, pipe bedding & concrete block wall base.*
  - *Lorusso-Bristol will furnish and deliver all required "fill" - 3/4" crushed stone, 3/4" dense graded & 1.5" dense graded.*

Answer: The understanding as indicated is confirmed. The contractor will coordinate with the manufacturer on the schedule for the quantity of material transported as indicated in the contract documents.

Prepared by: Woodard & Curran (Engineer)

Item No.	Unit or Lump Sum Price in Written Words	Estimated Quantity	Unit Bid Price	Extended Cost Figures
6	Survey Monitoring Platforms @ _____ Dollars and _____ Cents	15 EA		
7	Geotextile Fabric @ _____ Dollars and _____ Cents	~~12,700~~ 15,600 SY		
8	Install Precast Concrete Block Wall and Wall Under Drain @ _____ Dollars and _____ Cents	1 LS		
9	Spread & Compact Fill Material @ _____ Dollars and _____ Cents	40,650 Ton		
10	Trench Excavation Below Normal Grade @ _____ Dollars and _____ Cents	10 CY		
11	Rock Boulder Excavation @ _____ Dollars and _____ Cents	10 CY		